

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work: Estimate for Improvements to Roads and Drains at kattigenahalli Ambedakarnagara and Surrounding area in Ward no. 05

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	203.22	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	1801.80	Removing B.S Slab of Drain and stacking	Sqm	65.72	Rupees Sixty Five and Seventy Two Paise Only
3	1801.80	Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	80.56	Rupees Eighty and Fifty Six Paise Only
4	970.20	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete do- 7.5 cms thick	Sqm	665.68	Rupees Six Hundred Sixty Five and Sixty Eight Paise Only
5	252.00	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
6	126.00	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
7	1344.00	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	993.22	Rupees Nine Hundred Ninety Three and Twenty Two Paise Only
8	100.20	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5598.92	Rupees Five Thousand Five Hundred Ninety Eight and Ninety Two Paise Only

NO of corrections - ~~Three~~

E.E. (BTP. DIV)

Date
29/11

Quantity.	Description	Unit	Rates	
			In Figures	In Words
9 1554.00	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shuttering machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1856.67	Rupees One Thousand Eight Hundred Fifty Six and Sixty Seven Paise Only
10 445.22	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inclcuding loading and unloading. From 0.00 to 2.00 Km.	Cum	73.12	Rupees Seventy Three and Twelve Paise Only

No of corrections Nil

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
Jhath, Bangalore Mahanagara
30-11-17
Bangalore 92